

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of Work: Repair and Maintenance of Roads and Drains in Ward No. 11, (Kumarapalle)

Sl. No.	Approved Qty.	Description	Unit		
				In Figures	In Words
1	264.80	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	243.88	Rupees Two Hundred Forty Three and Eighty Eight Paise Only
2	38.10	Providing and laying Plain cement concrete of mix 1:3:6 with with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications and directions of engineer in charge of the work	Sqm Cum	5421.90	Rupees Five Thousand Four Hundred Twenty One and Ninety Paise Only
3	63.00	Providing laying plain / reinforced cement concrete for side drains using M 20 nominal mix concrete with OPC at 300 kgs with 20 mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed well compacted for walls and bottom including centering shuttering form work etc. complete as per approved drawing and design MORTH Specification No. 1500,1700,2200 Wall & Bottom thickness 15cm etc complete as per specifications and directions of engineer in charge of the work	Sqm Cum	7070.20	Rupees Seven Thousand Seventy and Twenty Paise Only
4	3.78	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. TMT bars Fe 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne Cum	90596.08	Rupees Ninety Thousand Five Hundred Ninety Six and Eight Paise Only
5	28.35	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chiselled dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5811.98	Rupees Five Thousand Eight Hundred Eleven and Ninety Eight Paise Only
6	54.00	Providing ruled pointing 20 mm deep coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specification	Cum	150.52	Rupees One Hundred Fifty and Fifty Two Paise Only

Sl. No.	Approved Qty.	Description	Unit		
				In Figures	In Words
7	19.50	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	cum Sqm	5599.98	Rupees Five Thousand Five Hundred Ninety Nine and Ninety Eight Paise Only
8	77.40	Providing precast slab of 100 mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge.	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
9	48.6	Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge.	Sqm	48.6	Rupees Forty Eight and Sixty Paise Only

[Signature]

Executive Engineer

Byatarayanapura Division

BBMP, Bangalore - 92

Note:

- 1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- 2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
- 3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- 4 Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))